

# Australasian Standard Project

## Room Data Sheets

<b>Department</b>	<b>Standard Components</b>	<b>Room Tag: 1390</b>
<b>Room Name</b>	<b>Bay - Mobile Equipment, 4 m2</b>	<b>Room Code: BMEQ-4</b>
<b>Area</b>	4.0 M2	
<b>No of Rooms</b>	1	
<b>Subtotal of Area</b>	4.0 M2	
<b>Hours of Operation</b>	24 Hours	
<b>Occupancy</b>	N/A	
<b>Also covers these Rooms</b>		
<b>Description/ Special Requirements</b>	<p>An open storage bay for one or more items of mobile equipment in frequent use which may include wheelchairs, mobile scales, commode chairs, patient lifting devices or other mobile equipment.</p> <p>Special Design Requirements: The Bay should be deep enough to ensure equipment stored does not impede corridor circulation; minimum depth 1200mm.</p> <p>Electrical equipment that requires recharging may be stored in this space whilst recharging, therefore provision of appropriately located power outlets will be required.</p>	
<b>Amendment</b>	31.10.03, - First Draft	

### Room Fabric and outline specifications

ID	Fabric	Material	Finish	Specification	Selection	Remarks
5010	Ceiling	Plasterboard	Paint, washable	Flush set, suspended		
6030	Cornice	Aluminium	Powdercoat	24mm shadow angle		
1000	Floor finish	Vinyl	Standard slip resistant	Seamless, coved		carpet optional
2000	Skirting	Vinyl	Prefinished	Floor vinyl coved, 150 mmH		or featheredge vinyl skirting over carpet
3000	Wall finish	Paint	Acrylic, washable			
4020	Wall protection	Composite	Prefinished PVC	Crash rail at 900 AFFL		Equal to 'Acrovyn'
4031	Wall protection	Composite	Prefinished PVC	Corner guards to 1500 AFFL		Equal to 'Acrovyn'
4022	Wall protection	Composite	Prefinished PVC	Crash rail at 350 AFFL		Equal to 'Acrovyn', optional

### Fittings and Furniture (FF)

ID	Description	Category	Group	Qty	Selection
7400	Trolley: equipment	Furniture/ Fitting	3	1	as required
24200	Wheelchair	Furniture/ Fitting	3	2	as required

### Fixtures, Equipment and associated Services (FE)

#### Services

ID	Description	Service Category	Qty	Remarks
5000	Airconditioning	HVAC		

**Australasian Standard Project**  
**Room Data Sheets**

**Department** | **Standard Components**  
**Room Name** | **Bay - Mobile Equipment, 4 m2**

**Room Tag:** 1390  
**Room Code:** BMEQ-4

ID	Description	Service Category	Qty	Remarks
6000	General fluorescent	Lighting		
9001	GPO: Double	Power	2	For recharging of electrical equipment