

Australasian Standard Project

Room Data Sheets

Department	Standard Components	Room Tag: 1420
Room Name	Bay - PPE (Personal Protective Equipment)	Room Code: BPPE
Area	2.0 M2	
No of Rooms	1	
Subtotal of Area		
Minimum Dimension	0.0 M2	
Hours of Operation	24 Hours	
Occupancy	N/A	
Also covers these Rooms		
Description/ Special Requirements	An open storage bay for location of personal protection equipment such as gloves, gowns, overshoes and masks.	
Amendment	31.10.03, - First Draft	

Room Fabric and outline specifications

ID	Fabric	Material	Finish	Specification	Selection	Remarks
5010	Ceiling	Plasterboard	Paint, washable	Flush set, suspended		
6030	Cornice	Aluminium	Powdercoat	24mm shadow angle		
1000	Floor finish	Vinyl	Standard slip resistant	Seamless, coved		
2000	Skirting	Vinyl	Prefinished	Floor vinyl coved, 150 mmH		
3000	Wall finish	Paint	Acrylic, washable			
4020	Wall protection	Composite	Prefinished PVC	Crash rail at 900 AFFL		Equal to Acrovyn
4031	Wall protection	Composite	Prefinished PVC	Corner guards to 1500 AFFL		As required; Equal to Acrovyn

Fittings and Furniture (FF)

ID	Description	Category	Group	Qty	Selection
3400	Coathook	Metalwork	1	2	
23950	Trolley	Furniture/ Fitting	3	2	for gowns, overshoes, masks etc

Fixtures, Equipment and associated Services (FE)

Services

ID	Description	Service Category	Qty	Remarks
5000	Airconditioning	HVAC		
6000	General fluorescent	Lighting		