

NSW Standard Project
Room Data Sheets

Department	Standard Components	Room Tag: 3340
Room Name	X-ray Viewing and Reporting	Room Code: XRRR
Area	12.0 M2	
No of Rooms	1	
Subtotal of Area	12.0 M2	
Hours of Operation	Available 24 Hours	
Occupancy	Up to 4	
Also covers these Rooms		
Description/ Special Requirements	Room within a Clinical or Diagnostic Unit for reviewing and reporting of patient imaging film or computerised images and to write reports.	
	Acoustics: Sound attenuation - medium; Acoustic privacy is required	
Amendment	09.12.03, - First Draft	

Room Fabric and outline specifications

ID	Fabric	Material	Finish	Specification	Selection	Remarks
5060	Ceiling	Acoustic	Prefinished	Drop-in tiles, 600x1200		
6030	Cornice	Aluminium	Powdercoat	24mm shadow angle		
8000	Door protection	Vinyl	Prefinished	Kickplate, 300mm high		
9002	Doors	Solid Core	Paint	Single leaf, half glazed		910mm clear opening, glazing optional
1149	Floor finish	Carpet	90/10 Wool/ Nylon	Broadloom; 48 oz.		vinyl also acceptable
7010	Observation	Glass	Clear	Through door/s		
2010	Skirting	Vinyl	Prefinished	Feather edged, 150 mmH		or floor vinyl covered skirting
3000	Wall finish	Paint	Acrylic, washable			

Fittings and Furniture (FF)

ID	Description	Category	Group	Qty	Selection
1120	Bench: workstation	Furniture/ Fitting	1	1	to 2 sides of room
2100	Chair: ergonomic, office	Furniture/ Fitting	3	4	
3350	Clock: battery operated	Furniture/ Fitting	3	1	
17255	Pedestal filing unit: mobile, 660mmH	Furniture/ Fitting	3	2	under bench
17310	Pigeon-hole unit	Furniture/ Fitting	1	2	above bench, vertical slots for X-Rays
17360	Pinboard: fabric covered	Furniture/ Fitting	1	2	above bench
24100	Waste bin: paper, 20 Litre	Furniture/ Fitting	3	2	under bench
24400	Whiteboard	Furniture/ Fitting	2	1	900x900, optional

Fixtures, Equipment and associated Services (FE)

ID	Description	Group	Qty	Ele	Data	CdW	HtW	WmW	Tap	Dns	Gas	Selection
11415	Computer: PACS	3	2	yes	yes	—	—	—	—	—	—	for computerised images
41100	Printer: networked	3	1	yes	yes	—	—	—	—	—	—	
54510	Telephone: handset, standard	3	4	—	yes	—	—	—	—	—	—	
69210	Xray viewer: multiscreen	3	2	yes	—	—	—	—	—	—	—	optional

NSW Standard Project
Room Data Sheets

Department | **Standard Components**
Room Name | **X-ray Viewing and Reporting**

Room Tag: 3340
Room Code: XRRR

Services

ID	Description	Service Category	Qty	Remarks
1006	Voice / Data outlet: double	Communications	4	1 outlet per workstation for telephone
1006	Voice / Data outlet: double	Communications	1	printer
5000	Airconditioning	HVAC		
6005	Dimmable	Lighting		for image viewing
6000	General fluorescent	Lighting		
6055	Special: task light, built in	Lighting	1	under O/H shelving
9001	GPO: Double	Power	9	2 per workstation + 1- printer
9060	Special: for equipment	Power	2	X-ray viewers (optional)