Department	Standard Components	**Room Tag:**	**1280**
Room Name	**Angiography Control/ Reporting Room**	**Room Code:**	**ANCRT-SJ**

Net Room Area Briefed	14.0 M2
No of Rooms	1
Subtotal of Briefed Area	14.00 M2
Hours of Operation	Available 24 Hours
Occupancy	Up to 3 staff
Also covers these Rooms	

Description/ Special Requirements	Room adjacent to Angiography Procedure Room/s with direct visibility to the patient for remote control of equipment, and review and reporting of procedure images. The Control/ Reporting room may serve two procedure rooms.
	
	Acoustics: Acoustic privacy is required
	
	Additional Design Considerations:
	  - Radiation shielding as advised by Radiation Consultant
	  - Cable ducts from Angiography Procedure Room and Computer/Equipment
	    room may be required

Amendment	13.03.2014 First issue

Room Fabric and outline specifications

ID	Fabric	Material	Finish	Specification	Selection	Remarks
5060	Ceiling	Acoustic	Prefinished	Drop-in tiles, 600x1200		
6025	Cornice	Aluminium	Powdercoat	shadow line		
8000	Door protection	Vinyl	Prefinished	Kickplate, 300mm high		
9004	Doors	Solid Core/ Glass	Paint	Single leaf, observation panel		920mm clear opening
1000	Floor finish	Vinyl	Standard slip resistant	Seamless, coved		
7025	Observation	Lead glass	Clear	Internal window		to procedure room
2000	Skirting	Vinyl	Prefinished	Floor vinyl coved, 150 mmH		
3000	Wall finish	Paint	Acrylic, washable			

Fittings and Furniture (FF)

ID	Description	Category	Group	Qty	Selection / Remarks
1050	Bench: laminate	Furniture/ Fitting	1	1	at 900H
1950	Chair: ergonomic, high	Furniture/ Fitting	3	3	
3400	Coathook	Metalwork	1	2	
17252	Pedestal drawer unit: mobile, 840mmH	Furniture/ Fitting	3	1	under bench
17360	Pinboard: fabric covered	Furniture/ Fitting	1	2	over bench
20000	Shelving unit: adjustable	Furniture/ Fitting	1	2	for books, manuals, over bench

Department	Standard Components	Room Tag:	**1280**
Room Name	**Angiography Control/ Reporting Room**	Room Code:	**ANCRT-SJ**

ID	Description	Category	Group	Qty	Selection / Remarks
24400	Whiteboard	Furniture/ Fitting	2	1	optional

Fixtures, Equipment and associated Services (FE)

ID	Description	Group	Qty	Ele	Data	CdW	HtW	WmW	Tap	Dns	Gas	Selection / Remarks
11400	Computer: PC & monitor	3	1	yes	yes	___	___	___	___	___	___	
62150	IMG: console, control	1	1	yes	yes	___	___	___	___	___	___	Angiography control monitors
41100	Printer: networked	3	1	yes	yes	___	___	___	___	___	___	
54510	Telephone: handset, standard	3	2	___	yes	___	___	___	___	___	___	on bench

Services

ID	Description	Service Category	Qty	Selection / Remarks
1040	Intercom	Communications	1	with handsfree microphone to Angio room
1006	Voice / Data outlet: double	Communications	5	3 outlets under bench for telephone
5000	Airconditioning	HVAC		
6000	General fluorescent	Lighting		
6055	Special: task light, built in	Lighting		under O/H shelving
9015	GPO: Cleaner	Power	1	
9001	GPO: Double	Power	8	
9060	GPO: Special: for equipment	Power	1	Angiography console equipment

SHCC Guidelines

Provided by TAHPI for :
Sharjah Domain

Issue No: 1

Issue Date: 1 Apr 2014

Print Date: 20 May 2014

Page 2 of 2