

<b>Department</b>	<b>Standard Components</b>	<b>Room Tag:</b>	<b>1310</b>
<b>Room Name</b>	<b>Assembly/ Collation/ Coding, 35m2</b>	<b>Room Code:</b>	<b>ASSCO-SJ</b>
<b>Net Room Area Briefed</b>	35.0 M2		
<b>No of Rooms</b>	1		
<b>Subtotal of Briefed Area</b>	35.00 M2		
<b>Hours of Operation</b>	8am to 6pm, daily		
<b>Occupancy</b>	Up to 6 staff		
<b>Also covers these Rooms</b>			
<b>Description/ Special Requirements</b>	The Assembly/ Collation/ Coding area is an open plan area use for processing the medical record prior to filing.		
<b>Amendment</b>	13.03.2014 First issue		

**Room Fabric and outline specifications**

ID	Fabric	Material	Finish	Specification	Selection	Remarks
5060	Ceiling	Acoustic	Prefinished	Drop-in tiles, 600x1200		
6025	Cornice	Aluminium	Powdercoat	shadow line		
1149	Floor finish	Carpet	90/10 Wool/ Nylon	Broadloom, 48 oz.		
2010	Skirting	Vinyl	Prefinished	Feather edged, 150mmH		
3000	Wall finish	Paint	Acrylic, washable			
7001	Windows					desirable

**Fittings and Furniture (FF)**

ID	Description	Category	Group	Qty	Selection / Remarks
1050	Bench: laminate	Furniture/ Fitting	1	2	sorting & collation; 900AFFL
2100	Chair: ergonomic, office	Furniture/ Fitting	3	6	
17250	Pedestal drawer unit: mobile, 660mmH	Furniture/ Fitting	3	6	under workstations
20000	Shelving unit: adjustable	Furniture/ Fitting	1	2	over benches
24440	Workstation: computer	Furniture/ Fitting	3	6	
24488	Workstation: partitions	Furniture/ Fitting	3	6	optional
24492	Workstation: shelf unit	Furniture/ Fitting	3	6	optional

**Fixtures, Equipment and associated Services (FE)**

ID	Description	Group	Qty	Ele	Data	Cd	WH	TW	Nm	WTap	Dns	Gas	Selection / Remarks
11400	Computer: PC & monitor	3	6	yes	yes	___	___	___	___	___	___	___	
11850	Computer: scanner	3	1	yes	yes	___	___	___	___	___	___	___	
41100	Printer: networked	3	1	yes	yes	___	___	___	___	___	___	___	
54510	Telephone: handset, standard	3	6	___	yes	___	___	___	___	___	___	___	to workstations

**Services**

ID	Description	Service Category	Qty	Selection / Remarks
----	-------------	------------------	-----	---------------------

Department

Standard Components

Room Tag:

1310

Room Name

Assembly/ Collation/ Coding, 35m2

Room Code:

ASSCO-SJ

ID	Description	Service Category	Qty	Selection / Remarks
1006	Voice / Data outlet: double	Communications	8	1 per workstation; 2 over benches
5000	Airconditioning	HVAC		
6000	General fluorescent	Lighting		
9015	GPO: Cleaner	Power	1	
9001	GPO: Double	Power	16	2 per workstation; 4 over benches for additional equipment