

Design Guidelines for Hospitals and Day Procedure Centres

Standard Components Room Data Sheets

| Room Name | Bay - PPE (Personal Protective Equipment) | Room Code BPPE |
|---------------------|---------------------------------------------------------------------------------------------------------------|----------------|
| Area M2 | 2 | |
| Description | An open storage bay for location of personal protection equipment such as gloves, gowns, overshoes and masks. | |
| Special Requirement | | |

Room Fabric and outline specifications

| | | | | | Remarks |
|------|-----------------|--------------|-------------------------|---------------------------|-------------------------------|
| 1000 | Floor finish | Vinyl | Standard slip resistant | Seamless, coved | |
| 2000 | Skirting | Vinyl | Prefinished | Floor vinyl coved, 150mmH | |
| 3000 | Wall finish | Paint | Acrylic, washable | | |
| 4020 | Wall protection | Composite | Prefinished PVC | Crash rail at 900mm AFFL | Equal to Acrovyn |
| 4030 | Wall protection | Composite | Prefinished PVC | Corner guards to 900H | As required; Equal to Acrovyn |
| 5010 | Ceiling | Plasterboard | Paint, washable | Flush set, suspended | |
| 6030 | Cornice | Aluminium | Powdercoat | 24mm shadow angle | |

Fittings and Furniture

| Fitting ID | Category | Fitting | Grp | Quantity | Selection |
|------------|-----------|----------------|-----|----------|-----------|
| 7200 | Metalwork | Equipment hook | 1 | 2 | |

Fixtures, Equipment and associated services

Services

| Service ID | Service Category | Description | Quantity | Remarks |
|------------|------------------|----------------------------------------|----------|-----------------------------------|
| 5000 | HVAC | Heating, Ventilation & Airconditioning | | Refer to Part E Building Services |
| 6000 | Lighting | General | | |